



ISO- 9001 : 2015

NATIONAL ACADEMY OF CONSTRUCTIONNAC Campus, Cyberabad, Kothaguda (Post), Hyderabad-500 084
Phone: 23111916 & 17, Fax: 23111997, e-mail: info@nac.edu.in**Notice No.NAC/ADMN/AD(AM)/ dated 03.10.2022.**

Sub:- NAC – ADMN – Notice inviting Quotations for Supply of RCC NP3 Pipes and related material for laying of Drainage Pipeline in NAC Campus, Hyderabad – Reg.

* * *

You are requested to submit quotations by 17.10.2022 at 03.00 PM for supply of RCC NP3 Pipes and related material for laying of Drainage Pipeline in NAC Campus, Hyderabad and the details is as follows

Sl. No	Description of Items	no's	Length (m)	Breadth (m)	Height (m)	Quantity	Total Quantity	Units	Rate per unit	Total Amount	Remarks
1	PCC bed(1:3:6) with 40mm HGBG metal for chambers	3	1.67	1.67	0.15	1.255	1.255	cu.m			
2	cement concrete bedding with M15(1:2:4) 20mm thick HBG metal	3	0.9144	0.9144	0.157	0.394	0.394	cu.m			
3	a)C/O Brick work for chambers with CM (1:4)	3	4.57	0.23	1.37	4.32	5.13	cu.m			
	b)C/O Brick work for Raising of chamber height for 2ft to retain soil from surroundings into the man hole	2	3.35	0.23	0.61	0.94					
	Deduction for pipe line portion	3	$(\pi/4)*(0.35)^2$		0.23	0.13					

4	RCC Slab to the chambers with M15 grade(1:2:4)with 20mm thick metal	3	1.37	1.37	0.2	1.13	0.91	cu.m				
	Deductions(for provision of CI COVER	3	0.61	0.61	0.2	0.22						
5	a)Plastering with CM(1:5) outside for raising the side walls above the chambers	2	3.04		0.61	3.71	21.55	sq.m				
	b)Plastering with CM(1:5) inside the chambers	3	3.66		1.22	13.4						
	C)Plastering with CM(1:5) outside the chambers for above G.L	3	5.48		0.3048	5.01						
	Deduction for pipe line portion	3 x 2	$(\pi/4)*(0.35)^2$			0.57						
6	cost of MS Steel for reinforcement including cost of bending & binding with cost of wire ,etc. complete	1				14.5	14.5	Kgs				
7	Supply of RCC S/S pipes NP3 300mm dia	1	22			22	22	rm				
8	CI covers(Heavy) for New 03 no's and existing 02no's Chambers of size (2ftx 2ft)	3				3	3	no's				
9	laying & jointing the pipes with CM(1:1)	9				9	9	each				
									Amount			
									Overhead charges @			
									Total			
									GST @			


	Sub-Total			
	CESS @ 1%			
	Total Amount			

This has the approval of DG, NAC

Terms & Conditions:

1. No other taxes are applicable.
2. The material shall be supplied within 02 days from the date of receipt of this supply order.
3. 100% payment will be made after supply of material within 07 days.
4. Contact person for the above work and payment is Mr. Md. N. Sikinder, Asst. Director (Assets Management), NAC and contact No. 9000567866 / 7989021125

Yours faithfully,


Director (Admin.), NAC
 3/10/22
 3/10/22

Copy to

The DG Peshi, NAC for favour of information.
 The Director (Finance), NAC for necessary action.

Copy to

The Asst. Director (Asset Management), NAC &
 The Instructor (Civil), HDI to follow up and complete the work.